

Package air-conditioner Optional parts Installation Manual of EXTERNAL LEV BOX PAC-SG95LE-E

[For CITY MULTI INDOOR UNIT 20-63 MODELS]

* Before installing the unit, make sure to read the installation manual of the indoor unit and this manual.

Safety precautions

· Before installing the unit, make sure to read all the "Safety precautions".

- These precautions provide very important points regarding safety. Make sure to follow them.
- Symbols used in this manual are categorized according to the degree of risk when used improperly as follows:

▲ Caution Precautions that should be observed to prevent injury or damage to the premises and/or contents thereof.

• After installation, perform the test run to ensure normal operation. Then explain the user the "Safety Precautions", use and maintenance of the unit based on the information in the Operation Manual. Both the Installation Manual and the Operation Manual must be given to the user. These manuals must always be kept by the actual users.

/ Warning

The unit must not be installed by the user. Ask the dealer or an authorized company to install the unit.

Installation must be properly done following this installation manual. • If the unit is installed improperly, water leakage, electric shock or fire may be caused.

• If the unit is installed improperly, water leakage, electric shock or fire may be caused.

Before installation (relocation) and electrical work

∧ Caution Use proper electrical cables to meet the standard for current Keep plastic bags away from children. capacity. · Children may put plastic bags over their head. And it may cause • If proper electrical cables are not used, short circuit, electric shock or suffocation fire may be caused. Make sure heat insulation for refrigerant piping is properly Perform drain piping according to the installation manual and installed to prevent bedewing. make sure water is drained properly and keep drain piping • Improper heat insulation may cause condensation on parts such as warm to prevent bedewing. pipings, and wet ceilings, floors or other valuable items. • If piping is not properly installed, water leakage may result, which will make the ceilings, floors or other household items wet.

1 Parts check This unit is provided with this manual and following parts in the box. Part ① External LEV Box ② Joint pipe ③ Pipe cover ④ Band 5 Fastener Q'ty 1 Cable(100mm) 2 2 6 2 Cable(5300mm) Figure Þ đđ


Note: Make sure to complete installation work of External LEV Box of optional parts before turning on the indoor unit. This unit may run improperly if the unit is not installed following this manual.


2 Installation procedure

Connect the External LEV Box to the liquid pipe and install it inside the ceiling (Do not install in an outdoor location. It may cause a breakdown). Make sure to install the access door on the ceiling.

2-1 Installation location

• The installation patterns below are available. Select the installation pattern according to the preferred installation method. The





MITSUBISHI ELECTRIC CORPORATION

